

Processing instructions V 11.0

ACCELERATOR No. 2

Note: This document describes the storage and application procedures for the setting **ACCELERATOR No. 2** for cementitious refractory concretes.

The instructions contained in this document must be complied with during processing and installation of the respective refractory concrete. Modification of or deviations from the processing instructions can lead to major problems during installation, and possibly to total failure of the installed refractory material. These instructions provide general guidelines for storage, processing, and installation of the specific refractory material. If, due to specific site conditions, it appears necessary to deviate from the procedures described here, please consult Refratechnik Steel GmbH before starting work.

Storage

- In general: Store under cool, dry, and frost-free conditions.
- The shelf life stated in the product information sheet is valid from the production date, and only if storage is in accordance with our recommendations. The production date is stated on the packaging label.
- Under certain circumstances, material that has been properly stored may still be usable even after expiry of the stated shelf life. In such a case, conduct a setting test with a sample before using the material. In case of doubt, the expired material can be checked by Refratechnik Steel GmbH.
- Incorrect storage can greatly reduce shelf life, and can impair product quality.
- The original pallet wrapping foil should be left intact for as long as possible to protect the product. However, the foil is not a substitute for storage under cover.
- Also standing water, e.g. due to inadequate drainage of the storage area, can damage the material.

- Stacking of the goods supplied by us (in sacks, Big Bags, etc.) is done under the sole responsibility of the shipping company or customer. Refratechnik Steel GmbH accepts no liability for possible consequential damage (damaged packaging, personal injury, etc.).

Health and safety

- Always wear suitable safety goggles, dust mask, protective clothing, and working gloves.
- Always wash thoroughly after working with the material.
- Observe the information in the safety data sheet.

General information

- This product is a setting accelerator for hydraulically setting refractory concretes. Delivered dry in buckets or other containers, the product is mixed dry on site with the refractory concrete whose setting is to be accelerated. Moreover, the accelerator shortens the on-site processing time of the respective refractory concrete.

- Before using the **ACCELERATOR No. 2**, please consult Refratechnik Steel GmbH to determine whether the product is suitable for the refractory concrete in question.
- Only use clean drinking water, as otherwise the setting behaviour may be affected.
- Low temperatures can retard or even stop the setting process. Therefore, the temperature of material and mixing water must be at least 5 °C. It might be necessary to heat the installation site.
- On the other hand, the setting process may be significantly accelerated at temperatures above 25 °C.
- Please take the expansion of the refractory material for your specific furnace application into account. The reversible and irreversible expansion values and the respective material properties are given in the product information sheet. Depending on the furnace operating conditions and the specific characteristics of the refractory material, any arising stresses and pressures must be compensated by suitably designed expansion joints.

- During installation of the monolithic refractory material, please ensure correct anchoring to the existing furnace structure and/or to the existing or adjacent refractory material (e.g. with steel anchors, ceramic anchoring systems, etc.).
- Suitable measures must be taken to ensure that the water or water vapour generated during the drying & heating up process is removed from the refractory lining without pressure build-up.
- With certain furnace structures and refractory linings, the drying process can cause water or water vapour to diffuse outwards in the direction of the furnace shell instead of inwards to the hot side (furnace chamber). Therefore, suitable measures must be taken to ensure that the water or water vapour can escape to atmosphere. For this purpose, 10-mm holes drilled into the outer furnace surface (at least 5 per m²) have proved to be successful.
- In order to ensure a continuous drying process, the entire furnace chamber

must always be flushed with an adequate amount of fresh air during the entire drying and heating up procedure. The air circulating in the furnace chamber may never be saturated with moisture.

Mixing

- Mixer, tools, conveying equipment, etc. must be clean and free from any form of contamination.
- Use of a positive mixer is essential.
- Proportioning instructions:
Based on the weight of the dry concrete material, the following amounts should be added:
Between 0,02 and max. 0,20 % by weight.
- Do not exceed the stated maximum amount.
- **ACCELERATOR No. 2** is mixed into the dry concrete material (mixing time: 30 seconds). Subsequently, continue mixing

in accordance with the processing instructions of the respective refractory concrete.

Processing

- Please observe the processing instructions for the refractory concrete in question.

Setting and curing

- Please observe the processing instructions for the refractory concrete in question.
- Use of **ACCELERATOR No. 2** will shorten the processing time, setting time, and time before formwork removal. These times can be determined by means of a trial mixture performed under on-site operating conditions.

Drying and heating up

- Please observe the processing instructions for the refractory concrete in question.